542/1476 Clyde-Riccarton-Wharanui Intersection



COSTS (Costs net of thirds-party contributions in brackets)

Total	Renewal	Backlog	Unallocated	Growth
\$409,756	\$81,951	\$140,956	0	\$186,849
(\$192,585)	(\$38,517)	(\$66,249)		(\$87,819)

COST ALLOCATION

Primary Driver:	Limited capacity means Level of Service will decrease Continued safety concerns
Secondary Driver:	
Capacity discussion:	
References:	

ATTRIBUTES

Project Manager:	tbc			
Work Planned:	Remarking, kerb and channel to allow alternative more- efficient and safer phasing			
Location:	Intersection of Clyde/Riccarton Rd/Wharanui			
Special features being addressed:				
A statement of the outcomes being addressed (LoS, Community Outcomes):	Improved network efficiency and capacity Improved Level of Service Improved Safety			
Options considered:				
Implications of not doing the project:	Limited capacity means Level of Service will decrease Continued safety concerns			
Linkages with other projects:				
Location of other relevant supporting information:				

SPM Project

Project Cost Allocation Summary

Background					
Project No	542/1476		Activity	Transport and City Streets	
Project Name	Clvde/Riccarton/Wharenui Intersection				
Project Manager	the				
Year first spend on the project	2007	Project Scope	tbc		
Year of first cost allocation	2006	,			
Year of current cost allocation	2006	-			
Project cost	\$409,756	-			
Level of Service Definitions		-	L		
Measure	Ratio	Primary Driver	tbc		
Existing Capacity	100.0				
Existing Demand	143.0	_			
Total Capacity	200.0	- Secondary Driver			
Design Capacity Year	2032				
End of Life Year	2047	-			
Backlog Capacity	43	Capacity Discussion			
Growth Capacity	57				
New Work Capacity	100	-			
% Backlog of New Work	43	- References			
% Growth of New Work	57				
Localities:		-			
	locality	nercentage com	ment		
	Riccarton W	est 100	linent		
On susting and Maintenance					
Operations and Maintenance	60				
O&M Cost Share	\$0	-			
Renewal	001.051				
Stand Alone Renewal Cost	\$81,951	_ Renewal Scope	Standard assumption f	or renewal component of Road Network Improvements	
New Works					
Stand Alone New Works Cost	\$409.756	New Works Scope	Standard assumption for	or new work component of Road Network Improvement	
	,		real and the second sec	r	
Renewal Cost Share	\$81,951	_			
New Work Cost Share	\$409,756				
Preliminary Cost Shares					
Backlog Cost Share	\$140,956				
Growth Cost Share	\$186,849	_			
Growth project		_			
Stand Alone Growth Cost	\$409,756	Growth Project Scope	Standard assumption for	or growth component of Road Network Improvements.	
Growth Cap	\$409,756				
		-			
Unallocated costs					
Unallocated Cost Share	\$0	_			
Project funding					
External Funding	\$217,171				
Summary of Cost Allocation		-			
		%	Total Cost	Net Cost	
O&M			\$0	\$0	
Renewal		20%	\$81,951	\$38,517	
Backlog		34.4%	\$140,956	\$66,249	
Growth		45.6%	\$186,849	\$87,819	
Unallocated		0%	\$0	\$0	
External Funding		L		\$217,171	
Project Total		100%	\$409,756	\$192,585	
		·			

TRANSPORT PROJECT SCOPING BRIEF

Project Initiator: CCC Transport Planning	Date: 23/1/2007
Project Name:	WBS if created: 542/1476
Clyde/Riccarton/Wharenui	
Background Data: (include project source – study, strategy, public enquiry, resource cor (include/append data needed for prioritisation process)	nsent, etc.)
Background report & simulation modelling results exist amongst Da files or in semi current library.	vid Robinson's as yet unpacked
B/C may/will need to formalised and submitted to LTNZ	
Date last reviewed: 23/1/2007	
Issue, Problem or Deficiency to be addressed:	
There is insufficient width on Riccarton Road to allow cycle lanes on intersections as part of the Riccarton Road traffic management sch this width it is not possible to separate the shared lanes through th signal phasing is required to be run resulting in long vehicle que potential safety concerns for cyclists.	this road through the two offset nemes along the route. Without ne intersection and an inefficient eues during peak periods, and
Date last reviewed: 23/1/2007	
Possible solutions/suggestions:	
(attach conceptual sketches , if appropriate)	
A conceptual scheme has been developed and drawn up by City Solu kerblines back within the intersection to allow the development of sep lanes. Location of scheme drawings unknown. Scheme work undert Baseplus funded by Capital Works Team. Date last reviewed: 23/1/2007	utions proposing to move the parate turn lanes and cycle aken Traffix 2005 Ltd &
Proposed Budget Category:	
Road Network Improvements Date last reviewed: 23/1/2007	
Priority Rating (if relevant):	
Project has high B/C, no designation required & relatively small capir for immediate construction because of this.	tal cost. Has been programmed
Date last reviewed: 23/1/2007	
Strategy or Strategic Objective(s) that the project will satisfy:- Congestion relief & cycling safety	
Date last reviewed: 23/1/2007	
Cost Estimate (include how this was derived and the level of acc \$440,989. Rough Order Cost, Oct 2006. See hardcopy develo background files (as yet unpacked David Robinson files). Date last reviewed: 23/1/2007 Note: This cost inflated for 2007/08 LTM	curacy and year of \$\$): per contributions worksheets & CCP.
Proposed Funding Method (for unbudgeted projects):	
Date last reviewed:	

¹ This is not to be a scheme plan drawn up by City Solutions, but more a transport planners pencil sketch that may be used for City Solutions to provide a Very Rough Order Costing if required. Its only purpose is for future reference as to what was the basis of the initial cost estimate. The project team should develop the scheme design.

S:\Transport Planning\Templates\Project Scoping Template\Project Scopes\2007_2008\Road Network

Improvements\Project Scope - Clyde Riccarton Wharenui.doc

Project Received by Capital Programme Team:

ande / RICCARTEN/ HARENUI

SCHEME ESTIMATE FORM

Project Name RICCARTON ROAD - STG 5			Charge Code			542/1096
Location Wharenui/Clyde	TATERSECTION			-		
Length	· MADELED	10-07.		Budg	et \$	-
Date 17-Jul-06	UPGRADE.		Schem	me Estimate \$		428,600
Construction Costs Associated with the Proje	<u>et</u>		н. 			
tem	Amount		and the second	-	PC CAL	CRESINCS
Kerb and Channel		17,956		(0		LIWEGTUS
Drainage		8,255				•
Sumps		8,349				
Waterway Enhancement		05 400				
Foopans		25,420				
Dusting Cabling						
Traffic Restraints / Islands						
Road Platform - Colour textured surfacing						
Landscaning		2,834				
Road Shoulders		38 515				
Carriageway Construction		20,010		•		
Shape Correction						
Road Markings		18.482				
Traffic Signs		300				
Street Furniture / Pedestrian Features		1.376				
Structures		60,000				
Carriageway Reseals, Shurry Reseals						
Water mains						
Traffic Control Etc	:	22,800				
			Construction Costs	Total		204,287
-			Contingency	25%		66,072
			Sub Total		\$	270,359
cillary Works Associated With The Project	•					
<u>m</u>	Amount					
Telecom Alterations (lower cables)		2,000				
Telstraclear Communications Alterations	1	15,000				
Orion Alterations (lower cables)		9,500		,		
Power / Light Pole Relocation		2,000				
Streetlighting (construction and fees)	,					
Water Supply Alterations	4	2,000				
Traffic Signal Alterations (poles)	2	1,000				
Traffic Signal Alterations (loops & cabinet)	L	./,100				
Landscape ex hursery		202	Ancillary Works	Total		88 983
:			Contingency	25%		22,246
			Sub Total	2070	\$	111.228
s Casts Associated With The Project			540 1044		Ψ	
n	Amount					381587
General Project Management	Altrain & second #					1
Base Plot						
Draft Scheme Development						
Survey legalisation						
Design	2	0,400				
Documentation	1	2,300				
Contract Administration & Supervision	1	4,300				
· · · · · · ·			Fees Sub Total		\$	47,000
	TOTAL PROJECT ES	TIMATE	9		\$	428,600
COMMENTS: *Base/Scheme Fees incl in	1 other section *Concrete Service	e Raft has f	50% Contingency			
*TELECOM*TELSTRA*	ORION ALL TO BE CONTAC	TED				
*ANCILLARY WORKS	PROVISIONAL SUMS ONLY					
	Verandas) NOT included *Fees	at 23%				
*Building Alterations (ie)			Date	: completed:	17	'-Jul-06
*Building Alterations (ie Completed by: Jane Campbell						
*Building Alterations (ie Completed by: <u>Jane Campbell</u>						12 4-0
*Building Alterations (ie Completed by: <u>Jane Campbell</u>				51	4 F FR	12, 402
*Building Alterations (ie Completed by: <u>Jane Campbell</u>				51	4 F FR	12, 402
<u>*Building Alterations (ie</u> Completed by: <u>Jane Campbell</u>				51	7 * I R ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	12, 402 + 140, 789

Note: costs shown here may have been inflated for 2007/08 LTCCP.